

\$135.20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20454-00-02
Spot: SWNW Sec/Twnshp/Rge: 22-1S-32W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: KASTENS Well #: 5
County: RAWLINS Total Vertical Depth: 4160 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	297	0	175 SX
PROD	4.5	4155	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2010 2:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 02/11/2010 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 297' w/175 sxs cement.
4 1/2" production casing set at 4155' w/150 sxs cement.
TD at 4160'. PBTD 4131'.
Perforated production casing at 2750' and 2175'.
Ran tubing to 2500' - pumped 180 sxs cement mixed with 600# hulls.
Pulled tubing to 1200' - pumped 100 sxs cement mixed with 200# hulls.
Cement to surface. Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 25 sxs cement.
Connected to 8 5/8" surface casing - pumped 45 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
4096	4099		
3996	4000		
3965	3976		

INVOICED
DATE 3/09/10
INV. NO. 2010060920

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #39117.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

JOHN O FARMER
RUSSELL KS 67665

22-01S-32W
C SW NW

5 KASTENS OWWO

site: 9-3/4 N & 7-1/4 E OF ATWOOD KS
contr: UNKNOWN

city: RAWLINS
field: WILHELM EAST

API 15-153-20454

geol:
 fr date 08/19/96 spd date 01/23/96 drig comp 01/23/96 card issued 08/19/96 last revised 08/19/96

ELV: 2980 KB, 2975 GL LOG
 tops.....depth/datum
 ANH.....2766 +214
 LANS.....3917 -937
 PBDT.....4131 -1151
 RTD OLD.....4160 -1180

IP status:
 INJ, LKC 3965-4099 OA, 01/24/96
 NOTE: CORR 6/10/87 - ADDED API & PF INTV
 OLD INFO: OPERATOR WAS JOHN O FARMER, 5
 KASTENS, SPD 08/03/82, 08/09/82 8-5/8" 297 / 175 SX,
 4-1/2" 4155 / 150 SX, OIL, P 60 BOPD, LKC 3965-4099 OA,
 09/14/82 (CARD ISSUED 11/04/82)
 CONTR: JOHN O FARMER
 NO CORES
 DST (1) 3930-4010 (SHAW, LKC), / 45-45-45-45, REC 315'
 OCM ISIP 1001# FSIP 954# IFP 152# -162# FFP 171#
 -190#

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

JOHN O FARMER
RUSSELL KS 67665

22-01S-32W
C SW NW

5 KASTENS OWWO

DST (2) 4065-4110 (LKC), / 45-45-60-60, REC 145' MDY OIL ISIP 734# FSIP 725# IFP 66# -76#
 FFP 85# -104#
 MICT - CO, PF (LKC) 3965-3976, 3996-4000, 4096-4099, W / 4 SPF, AC 3000 GAL (28% NE), SWB
 LD, SET 2-3/8" TBG & PKR AT 4071, POP, P 60 BOPD, 9/14/82
 NEW INFO: FR 08/19/96, REWORKED 01/23/96 DC 01/23/96 MICT - CO, PB 4131, TSTD OLD PFS
 (LKC 3965-4099 OA), CONVERTED TO WIW - INJECTION RATE SATISFACTORY, 1/24/96

replacement card

JOHN O. FARMER, INC.
RUSSELL, KS 67665

22-01 -32W
C SW NW

5 KASTENS

site: 9-3/4 N & 7-1/4 E OF ATWOOD, KS
contr: JOHN O. FARMER, INC.

city: RAWLINS
field: WILHELM EAST

API 15-153-20454

	+	+
	+	+
	+	+

geol:
 fr date 07/26/82 spd date 08/03/82 drig comp card issued 11/04/82 last revised 06/10/87

ELV: 2980 KB LOG
 tops.....depth/datum
 ANH.....2766 +214
 LANS.....3917 -937
 RTD.....4160 -1180

IP status:
 OIL, P 60 BOPD, LKC 3965-4099 OA,
 CSG: 8-5/8" 297 / 175 SX, 4-1/2" 4155 / 150 SX
 NO CORES
 DST (1) 3930-4010 (SHAW, LKC), / 45-45-45-45, REC 315'
 OCM ISIP 1001# FSIP 954# IFP 152# -162# FFP 171#
 -190#
 DST (2) 4065-4110 (LKC), / 45-45-60-60, REC 145' MDY
 OIL ISIP 734# FSIP 725# IFP 66# -76# FFP 85# -104#
 MICT - CO, PF (LKC) 3965-4099 OA, W / 4 SPF, AC 3000
 GAL, SWB LD, T&R, POP, P 60 BOPD, 9/14/82

CORRECTION: 6/10/87 - ADDED API & PF INTV

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS