

#183,63

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20910-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 16-32S-26W  
1100 feet from S Section Line, 1300 feet from E Section Line  
Lease Name: LAUPPE Well #: 16-1  
County: MEADE Total Vertical Depth: 5650 feet

Operator License No.: 31790  
Op Name: FREMONT EXPLORATION, INC.  
Address: 12412 SAINT ANDREWS DR  
OKLAHOMA CITY, OK 73120

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	995		WITH 410 SX CMT
PROD	2.875	5650	2317	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2010 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: FREEPOINT CASING, PULL OUT & TEST CASING. AT FREEPOINT PUMP 200# HULLS, MUD, 50 SX CMT. TAG PLUG. LOAD HOLE WITH MUD, PLUG AT 1980' WITH 50 SX CMT. PLUG AT 1020' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2010 11:40 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 2317' WITH 200# HULLS & 50 SX CMT. TAGGED AT 2180'. 2ND PLUG PULL TO 1980' & PUMP 50 SX CMT. 3RD PLUG AT 1020' WITH 50 SX CMT. 4TH PLUG PULL TO 600' & PUMP 40 SX CMT. 5TH PLUG PULL TO 40' & PUMP 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5470	5486		

INVOICED  
DATE 3/09/10  
INV. NO. 2010060922

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: USED COMMON CEMENT BY SARGENTS.

MAR 08 2010

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

MAR - 2 2010

KCC DODGE CITY

Signed

*Jerry W. Stapleton*  
(TECHNICIAN)

Form CP-285