

\$ 158.73

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21005-00-00
Spot: NWSESW Sec/Twnshp/Rge: 3-35S-12W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LOHMANN Well #: 5-A
County: BARBER Total Vertical Depth: 4884 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	329		
PROD	4.5	4883	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2010 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: VRATIL SERVICES Phone: _____

Proposed Plugging Method: RUN TBG TO 4000' & PUMP 50 SX COMMON CMT W/2% CC. PERFORATE @ 600'. RUN TBG TO 600' CIRCULATE CMT UP 4 1/2" & 8 5/8" X 4 1/2".

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 02/18/2010 10:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

TOP OF FISH (JUNK) @ 4082'. SPOT 50 SX COMMON CMT W/3% CC THROUGH TBG AT 4000'. TAG PLUG AT 2547'. PERFORATE 4 1/2" CASING AT 600'. RUN TBG TO 600'. FILLED 4 1/2" CASING & CIRCULATED CMT TO SURFACE ON 4 1/2 X 8 5/8" ANNULUS WITH 215 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4825	4831		

INVOICED
DATE 3/09/10
INV. NO. 2010060924

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 01 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
FEB 18 2010
KCC DODGE CITY

Form CP-24