

\$170.76

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20336-00-01
Spot: NWSW Sec/Twnshp/Rge: 16-30S-19W
1948 feet from S Section Line, 4758 feet from E Section Line
Lease Name: BENDER A Well #: 3
County: KIOWA Total Vertical Depth: 5254 feet

Operator License No.: 33388
Op Name: J. MARK RICHARDSON FAMILY TRUST
Address: 1406 N CHARLES
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	654		WITH 400 SX CMT
PROD	4.5	5253	2018	WITH 100 SX CMT

Well Type: SWD UIC Docket No: D18512.0 Date/Time to Plug: 02/23/2010 12:20 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4730' WITH 2 SX CMT. PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2010 5:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG & PACAKER TO 3750'. PUMPED 25 SX CMT W/2% CC. TOC @ 3675'. 1ST PLUG AT 1220' WITH 15 SX GEL, 50# HULLS, & 50 SX CMT. 2ND PLUG AT 680' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5225	5228		
5206	5214		
5162	5165		
5142	5148		
5115	5118		
5096	5098		
4739	4745		

INVOICED
DATE 3/09/10
INV. NO. 2010060927

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR - 2 2010
KCC DODGE CITY

Form CR-2/3