

\$ 158.08

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-00583-00-01

Spot: SWSW

Sec/Twnshp/Rge: 19-30S-33W

660 feet from S Section Line,

660 feet from W Section Line

Lease Name: SWLVLU

Well #: 34

County: HASKELL

Total Vertical Depth: 4864 feet

Operator License No.: 32309

Op Name: PRESCO WESTERN LLC

Address: 5665 FLATIRON PKWY  
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4050		WITH 2 SX CMT
CIBP		4144		WITH 2 SX CMT
SURF	8.625	765		WITH 700 SX CMT
PROD	5.5	4864		WITH 200 SX CMT

Well Type: EOR

UIC Docket No:

Date/Time to Plug: 01/22/2010 8:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: STEVE RIDENOUR

Company: PRESCO WESTERN

Phone: (303) 444-8881

Proposed Plugging Method: CIBP @ 4060' WITH 2 SX CMT OR PUMP 15 SX GEL & 200# HULLS. PRESSURE UP. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 810' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/22/2010 10:30 AM

KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*SQUEEZED 4389-4392 & 4148-4150\*\* CIBP @ 4144' WITH 2 SX CMT. CIBP @ 4050' WITH 2 SX CMT. TESTED 5 1/2" CASING TO 350 PSI. 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. PUMP 25 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN PRESSURE 350 PSI.

Perfs:

Top	Bot	Thru	Comments
4389	4392		
4148	4150		
4135	4137		
4123	4129		
4113	4118		

INVOICED  
DATE 3/09/10  
INV. NO. 2010060931

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 01 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

FEB 18 2010

KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)