

\$139.75

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22256-00-01
Spot: N2SWSWSE Sec/Twnshp/Rge: 21-15S-22W
540 feet from S Section Line, 2310 feet from E Section Line
Lease Name: RUFF Well #: 1-21
County: TREGO Total Vertical Depth: 4300 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	229	0	165 SX CMT COMMON 2% GEL, 3% CC
T1	2.875	4207		
PROD	5.5	4298	0	130 SX CMT AA-2 10% SALT, 5% CALSEAL, .8% FLA 322, .25 CELL FLAKE

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2010 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING COMP Phone: (620) 617-3357

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel- 500# hulls - 15 sxs gel. DV Tool at 1607' with 250 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2010 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4185' - pumped 85 sxs cement with 300# hulls.
Pulled tubing to 3440' - pumped 15 sxs gel.
Pulled tubing to 1875' - pumped 100 sxs cement.
Pulled tubing to 925' - pumped 60 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - squeezed - shut in with 200# P.S.I. - full.
Topped off 5 1/2" with 10 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
4164	4172		
4154	4164		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 3/09/10
INV. NO. 2010060923

Remarks: SWIFT CEMENTING COMPANY-TICKET #17420.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

MAR 02 2010

