

219.38

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22575-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 14-34S-38W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: MID AMERICA CATTLE Well #: 14 1
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6156		WITH 2 SX CMT
CIBP		6230		
CIBP		6500		
SURF	8.625	1675		WITH 670 SX CMT
PROD	5.5	6747	1790	WITH 330 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2010 11:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET 5 1/2" CIBP @ 6156' W/2 SX, CUT/PULL CSG @ FREEPOINT, SET CMT PLGS @ 1725' W/ 100 SX, @ USEABLE WTR DEPTH W/ 50 SX, AND @ 50' TO SURF W/ 15 SX OR PLUG PER KCC GUIDELINES & REGULATIONS

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2010 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 6156' WITH 2 SX CMT. 1ST PLUG AT 1725' WITH 100 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 50' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6552	6562		
6535	6540		
6247	6261		
6236	6245		
6206	6222		

RECEIVED
MAR 04 2010
KCC WICHITA

INVOICED
DATE 3/09/10
INV. NO. 2010060918

Remarks: USED 60/40 POZMIZ 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
FEB 26 2010
KCC DODGE CITY

Signed Jack MacLaskey
(TECHNICIAN)