

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00810-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 25-12S-22W
330 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: OGALLAH UNIT Well Number: 7-1
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 3455 (6569)
Op Name: SCHMITT, CARMEN
Address: 14 CIRCLE DRIVE P.O. Box 47
BELOIT, KS 67420 Great Bend, Ks 67530

Production Casing Size: 5.5 feet: 4036 175 SX CMT
Surface Casing Size: 8.625 feet: 518 275 SX CMT 131.30

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/18/2003 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 250 sxs cement - 500# hulls. - 17 sxs gel.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/18/2003 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. 518' w/275 sxs cement. 5 1/2" casing at 4036' w/175 sxs cement.
Squeezed at 1121' to 1161' w/100 sxs cement (1957).
Squeezed at 1259' w/100 sxs cement (1955).
Ran tubing to 3600' - spotted 17 sxs gel with 200# hulls - 30 sxs cement with 200# hulls.
Pulled tubing to 1400' - circulated with 125 sxs cement.
Pulled all tubing and squeezed with 30 sxs cement.
Max. P.S.I. 600#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" and squeezed 35 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.
Total of 220 sxs 60/40 pozmix - 10% gel - 500# hulls - 17 sxs gel.
Dakota 643'-943'. Anhydrite 1760'-1800'. Salt 2110'-2260'.

RECEIVED
03-06-2003
MAR 06 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS CHURCH #1. ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L Moses
(TECHNICIAN)

INVOICED

DATE 3-6-07

INV. NO. 2003061224

Form CP-2/3

MAR 03 2003

Ogallah Unit 7-1


TEXAS COMPANY #1 CHURCH 25-12-22W
SW SW SW

Contr. _____ TREGO _____ County

E 2348 Comm. _____ Comp. 10-26-51 IP 3000 BOPD (ARB)
DRAW DOWN

Tops	Depth	Datum
HEEB	3575	-1227
LANS	3608	-1260
ARB	4008	-1660
T.D.	4040	-1692

Casing
 8" 518 DP 4036;
 5" 4036 PERF 20 S, 4008-20
 600' WTR & 600' OIL/
 1/2 HR:
 SWB 41 BOPH;
 PERF 52 S, 4020-34
 SWB 67 BOPH



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS