

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00814-00-00
Spot: CSWSWNW Sec/Twnshp/Rge: 25-12S-22W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: OGALLAH UNIT Well Number: 7-5
County: TREGO Total Vertical Depth: 4018 feet

Operator License No.: 3455 6569
Op Name: SCHMITT, CARMEN
Address: 14 CIRCLE DRIVE P.O. Box 47
BELOIT, KS 67420 Grant Bend. ks 67530

Conductor Pipe: Size feet: \$130.59
Surface Casing: Size 8.625 feet: 496 350 SX CMT
Production: Size 5.5 feet: 4014 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/19/2002 11:00 AM
Plug Co. License No.: 6569 Plug Co. Name: SCHMITT, CARMEN, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2002 1:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 496' w/350 sxs cement. 5 1/2" casing at 4014' w/175 sxs cement.
Squeezed 5 1/2" at 1010' w/100 sxs cement (1953).
Tied to 5 1/2" casing and squeezed 400 sxs cement and 400# hulls.
Max. P.S.I. 600#. S.I.P. 400#.
Tied to 8 5/8" x 5 1/2" annulus and squeezed 125 sxs cement and 100# hulls.
Max. P.S.I. 250#. S.I.P. 200#.
Total of 525 sxs 60/40 pozmix - 10% gel and 500# hulls.
Dakota at 640' - 940'. Salt Section at 2110' - 2260'. Anhy at 1760' - 1800'.

RECEIVED
01-03-2003
JAN 03 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS CHURCH #5. COPELAND ACID/CEMENT. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

DATE

1-3-03

INV. NO.

2003061025

Form CP-2/3

DEC 30 2002

TEXAS COMPANY

#5

CHURCH

25-12-22W
SW SW NW

Contr. NOBLE DRILLING COMPANY

TREGO

County

E 2345RB

Comm.

Comp.

3-14-52

IP

79 BOPD & 160 BW
PHY POT (ARB)

Tops	Depth	Datum
TOP	3399	-1054
HEEB	3595	-1250
LANS	3624	-1279
ARB	4013	-1668
T.D.	4027	-1682

Casing

8" 496 DD 4022: 14 GOPH:
 5" 4013 DD 4025: 17 GOPH:
 WTR: PB 4025:
 PB 4018:
 PMP 26 B0 & 53
 BW/8 HRS

OGALLAH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS