

4-032278

15-195-01446-00-00

12-10

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1952

SW SE SW /4 SEC. 25, 12, 22 W  
330 feet from S section line  
3630 feet from E section line

Operator license# 6569

Lease: Ogallah Unit Well # 8-1

Operator: Carmen Schmitt

County: Trego 132.60

Address: P.O. Box 47  
Great Bend, Kansas 67530

Well total depth 4080 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 10 Month: December Year: 1997

Plugging proposal received from: Carmen Schmitt

Company: Carmen Schmitt Phone: -

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:45 P.M., Day: 10 Month: December Year: 1997

Actual plugging report: 8 5/8" set at 208' w/150 sxs cwc. 5 1/2" set at 4080' with 110 sxs  
D.V. Tool at 1743' with 900 sxs cwc. Prod. Perfs 4000' - 4032'. Ran tubing to 1068' top of  
fish. Mixed and pumped 130 sxs cement blend with 500# hulls to circulate. Pulled tubing.  
Squeezed 5 1/2" with total 230 sxs cement blend and 500# hulls mixed in to Max. P.S.I. 800#.  
Close in 500#. Squeezed 8 5/8" to 300# cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING Elevation: GL

I did X did not [ ] observe the plugging.

Carl Goodrow  
(agent)

Dec. 18, 1997

INVOICED  
DATE JAN 06 1998  
INV. NO. 49843  
12-10