

6 030706

206
15-195-0081700-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW SWSE, SEC. 25, T. 12 S, R. 22 W

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line

2310 feet from E section line

Operator License # 5153

Lease Name Ogalla Unit Well # 9-1

Operator Name & Address Jefaco Inc.

County Irego 130.13

Rt 2 Box 201

Well Total Depth 4004 feet

Great Bend, Kansas

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 515'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Kansas

Company to plug at: Hour: PM Day: 15 Month: 4 Year: 19 86

Plugging proposal received from Roy Hoover

(company name) Jefaco Inc. (phone) _____

were: 8 5/8 @ 515' w/ 325sx. 5 1/2 @ 3969 w/ 175sx. Squeezed @ 1116' w/ 150sx

& @ 1463' w/ 150sx. PBDT 3978 OPEN HOLE arb. Junk bridge @ 48'

Rig up and drill out plug. Circulate clean. Order 250 sx.

Econo-lite ALC 6sx. Hulls. Allied Cement. Co. Wellrock
Water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:PM Day: 15 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Hook up to 5 1/2" mix & pump 4 hulls - (88 hulls)

220sx. Cement mix + 2sx. hulls. loaded hole & squeezed

Max. P.S.T. 400# close in 200#

Hook up to back side annulus mix & pump 20 barrels
of slurry (30sx. mix) Max P.S.T. 600# close in 200#

Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____ (if additional description is necessary, use BACK of _____)

INVOICED
DATE APR 29 1986

I (did/did not) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13605

4-15