

6 030707

15-195-00818-00-00²⁰⁹ R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SESWSE, SEC. 25, T 12 S, R 22 W

330 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Ogalla Unit Well # 9-2

Operator: Jexaco Inc.

County Jrego 130.16

Name & Address Rt. 2 Box 201

Well Total Depth 4005 feet

Great Bend, Kansas

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 492'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Kansas

Company to plug at: Hour: PM Day: 15 Month: 4 Year: 19 86

Plugging proposal received from Roy

(company name) Jexaco Inc. (phone) _____

Size: 8 5/8 @ 492' w/ 325 sq 5 1/2 @ 3977' w/ 175 sq. Squeeze @ 1153' w/ 150 sq
Open Holes avail. Fluid level 300' Order 250 sq Ciono-lite
ABC Cement mix. 6 sq hulls Allied Cement Co. Wellrock
water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 PM Day: 15 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Hook up to 5 1/2" mix & pump 4 sq. hulls. (3 barrels)
3 barrels (220 sq. cement) cement slurry loaded hole & squeezed
max PSI. 1000# close in 300#

Hook up to backside (annulus) mix & pump (20 barrels)
30 sq cement mix slurry load & squeeze max PSI 300#
close in 200# Plug Complete.

Remarks: (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

APR 28 1986

CONSERVATION DIVISION
Wichita, Kansas
4-25-86

WITNESSED (I did not) observe this plugging.

DATE APR 29 1986

Signed Carl Goodrow
(TECHNICIAN)

DATE

REV. NO. 13606 4-15 MAY 28 1986