

1-21

4-032203

15-065-03152-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1960

SW NE NE /4 SEC. 10, 10, 25 W  
4290 feet from S section line  
990 feet from E section line

Operator license# 3553

Lease: Elrick Well # 13-2

Operator: Citation Oil & Gas Corporation

County: Graham

Address: 8223 Willow Place South  
Suite #250  
Houston, Texas 77070

Well total depth 4238 <sup>137.73</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 196 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 21 Month: January Year: 1997

Plugging proposal received from: Citation Staff - Attn: Chris Morro

Company: Citation Oil & Gas Corporation Phone: \_\_\_\_\_

Were: Order 225 sxs 60/40 pozmix - 6% gel - 500# hulls.  
Halliburton Cement Company.

1-30-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:30 P.M., Day: 21, Month: January, Year: 1997

Actual plugging report: 8 5/8" set at 196' w/165 sxs cwc. 4 1/2" set at 4237' with 50 sxs cement and 600 sxs latex. Prod. Perfs 3760' - 4230'. PBSD 4050'. CIBP 4050'. Bridge at 2060'. Critical control shots at 2060' and 1250'. Free at 1120'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 250'. Mixed and pumped 80 sxs cement to circulate. Pulled casing. Topped off with 20 sxs cement. Plug complete.

Remarks: Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ GL

I did  did not  observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

INVOICED

DATE 2-3-97

INV. NO. 47494