

15-065-03144-0000

4-031995

10-20

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - N/A

NW NE SE /4 SEC. 10, 10 S, 25 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 3553 Lease Elrick well # 6-6

Operator: Citation Oil & Gas Corporation County Graham

Address: 4848 SW 36th Street Well total depth 4255 feet  
Oklahoma City, OK 73179 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 153 feet

138.29

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 20 Month: October Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone:           

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:00P.M., Day: 20, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 153' w/115 sxs. cwc. 5 1/2" set @  
4036' w/100 sxs. Prod. perfs. 3795' - 3990'. O.H.4036'-4255'. C.I.B.P.  
3700'. Beat C.I.B.P. down hole. Sand back 3700' w/5 sxs. common cement  
on sand with bailer. Critical area control shots at 2136' - 1259' and  
free at 1125'. Mixed and pumped 150 sxs. cement blend with 300# hulls  
to 2136' with Max. P.S.I. 600#. Pulled casing to 200' circulated with  
40 sxs. cement blend with 200# hulls mixed in. Pulled casing topped off.  
8 5/8" with 10 sxs. cement blend. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1994

CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Condition of casing(in hole):GOOD X BAD     Anyh.plugin:YES X NO      
Bottom plug(in place):YES X, CALC    , NO     Dakota plug:YES X NO      
Plugged through TUBING    , CASING X. Elevation:     GL    

I did not observe the plugging. Carl Goodrow

DATE 11-8-94  
INV. NO. 416012

(agent)  
Form CP-2/3