

8-26

4-041522

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-03245-0000

SW SW SW /4 SEC. 10, 10 S, 25 W
330 feet from S section line
4950 feet from E section line

Operator license# 3553 Lease Elrick well # 7-8

Operator: Citation Oil & Gas Corporation County Graham

Address: 8223 Willow Place S. Well total depth 4005 feet ^{130.16}
Suite 250 Conductor Pipe: 0 inch @ 0 feet
Houston, Texas 77070 Surface pipe 8 5/8 Inch @ 148 feet
w/100 sx cwc.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 25 Month: August Year: 93

Plugging proposal received from: Jeff Uecker - Verlan Duggan

Company: Citation Oil & Gas Corporation Phone:

Were: 5 1/2" casing set @ 4004' w/100 sx.s.cement. Perf. @ 3764'-3988'.
Anhy. @ 2150' - Dakota @ 1248' - W.L.M. 3998'.
Ordered 625 sx.s. 60/40 pozmix - 6% gel with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 4:00P.M., Day: 26, Month: August, Year: 93

Actual plugging report: R.I.H. with tubing. Spotted 90 sx.s. cement with 400# hulls @ 3980'. Spotted 10 sx.s. cement with 200# hulls @ 2156'.
Pull to 1250' circulate cement to surface with 130 sx.s. cement. Pulled tubing. Hooked-up to 5 1/2" casing, squeezed 150 sx.s. cement.
Max. 600# P.S.I. Hooked-up to 8 5/8" S.P. Squeezed 150 sx.s. cement.
Max. 600#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X did not observe the plugging.

Dennis L. Hamel
ND (agent)

RECEIVED CORPORATION COMMISSION

OCT 20 1993

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-21-93
38994