

4-071106

8-2

15-065-03147-0001

E-14,576

API number: 15- - 11-7-58

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE /4 SEC. 10, 10 S, 25 W
3630 3960 feet from S section line
PT 1650 feet from E section line
KCC

Operator license# 3553 Lease Elrick Unit well # 12-3

Operator: Citation Oil & Gas Corporation County Graham

Address: 8223 Willow Place - Suite #250 Well total depth 4242 feet
Houston, Texas 77070 Conductor Pipe: 0 inch @ 0 feet
Tim Crabtree Surface pipe 8 5/8 Inch @ 156 feet

137.87

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Allied Cementing - Leiker Rig License# -

Address: Oakley, Kansas - Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 2 Month: August Year: 94

Plugging proposal received from: Tim Crabtree - Dennis Hamel

Company: Citation Oil & Gas - KCC Phone: 713-469-9664

Were: 8 5/8" - 156' S.P. cwc w/100 sxs. cmt. 5 1/2" casing set @ 4232'
w/200 sx.cmt. D.V. tool set @ 2211' w/100 BBL's of K - CIBP @ 4022'-3640'.
Perfs. 3777'-4002' - Elv.2516' - Citation pushed CIBP form 3640' - 3903'.
Proposal 575 sxs.class A common - 6% gel and 5 sxs. hulls. Spot and displace
all cement through tubing. Load both 5 1/2" casing and 5 1/2" x 8 5/8"
annulus with cement from top to bottom. Shut in under pressure. Perforate
5 1/2" casing at 2150' and 1240'.

Plugging Proposal Received by: Dennis Hamel - Marion J. Schmidt
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:35 P.M., Day: 2, Month: August, Year: 94

Actual plugging report: Citation ordered 575 sxs. class A common - 6% gel
and 500 lbs. of cotton seed hulls. Pumped in all cement with pump truck.
Spotted and displaced all cement through tubing.

- 1) L.K.Wireline perforated 5 1/2" casing at 2150' - 1240'.
- 2) 2 7/8" tubing @ 3900' - spotted and displaced 200 sxs.cmt w/4 sxs.hulls added.
- 3) 2 7/8" tubing @ 1600' - spotted w/175 sxs.cmt. - cement circulated out of 5 1/2" casing.
- 4) Squeezed 5 1/2" x 8 5/8" annulus w/150 sxs.cmt. Max.pressure 200# P.S.I. Shut in 100# P.S.I.
- 5) Squeezed 5 1/2" casing w/30 sxs.cmt. Max.pressure 500# P.S.I. Shut in @ 300# P.S.I.

Remarks: Cemented by Allied Cement - Oakley, Kansas
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2516 GL

I did not observe the plugging.

Marion J. Schmidt

(agent)

Form CP-2/3

INVOICED

DATE 8-26-94

INV. NO. 41020

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
8-14-94
AUG 17 1994