

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03146-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 10-10S-25W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: KNOLLB Elrick Unit Well Number: 12-2
County: GRAHAM RTKCL Total Vertical Depth: 4250 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

Conductor Pipe: Size _____ feet: 8 138.13
Surface Casing: Size 8.625 feet: 156 100 sx
Production: Size 5.5 feet: 4236 200 sx
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2002 10:00 AM

Plug Co. License No.: 3553 Plug Co. Name: CITATION OIL & GAS CORP.

Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS CORP. Phone: (785) 623-1557

Proposed Plugging Method: Emergency plug with rig over the hole.
Fish at 2616' - packer - 12 joints tubing.
Squeezed at 2261' w/200 sxs cement.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/15/2002 2:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

02-12-2002 - TIH with tubing to 2265' w/retainer plug.
Tied onto and pumped 250 sxs Class A Common 1/4 floseal and displaced with 8 1/2 bbls.
Let set up 4 hours - pressured up to 500#.
06-15-2002 - TIH with tubing to 2265' and spotted 100 sxs with 250# hulls.
Pulled up to 950' and circulated cement with 80 sxs cement and 250# hulls.
Hooked onto 8 5/8" and pumped 50 sxs cement. S.I.P. 300#.

RECEIVED
6-21-02
JUN 21 2002
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS ELRICK UNIT #12-2. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-24-02

INV. NO. 2002061999

JUN 19 2002

EMPIRE DRLG & N C R A

#2 KNOLL 'B'

i 0-10-25w
SW NW NE

Contr. EMPIRE DRLG

GRAHAM County

E 252 LRB Comm 1-27-59 Comp 2-27-59 IP

199 BOPD
PHY POT

Tops	Depth	Datum
ANH	2167	357
HEEB	3759	-1235
TOR	3778	-1254
LANS	3800	-1276
B/KC	4034	-1510
CHERO	4224	-1700
CHERO LM	4230	-1706
TD	4250	-1726

Casing

8" 156

5" 4236

DST 3768-85/1 HR, 60' OCM, BHP 1300#

DST 3786-3805/1 HR, 810' SL GSY & OILY SW,
BHP 1360#

DST 3814-30/75", G/29", 2370' O, BHP 1300#

DST 4236-50/1 HR, 1980' G, 700' O, 20'
H OCM, BHP 1140#

CO TD: 8 BOPH/8 HR, NATL: ACID 3000: SWB

33 BOPH/6 HR: PB 4022: PERF 4000-06: SWB

8 GO: ACID 3000: SWB 15 BFPH/5 HR: PB

3990: PERF 3978-84: ACID 3000: SWB 15

ELRICK POOL

BFPH: PB 3960: PERF

3934-40: ACID 3000: CO 4052
BFPH/4 HR: SWB 30 BFPH/5 HR

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS