

10-30

4-041341

15-065-03143-0001

57
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 12-12-58

NW SE SE /4 SEC. 10, 10 S, 25 W
990 feet from S section line
990 feet from E section line

Operator license# 3553

Lease Elrick Unit well # 6-5

Operator: Citation Oil & Gas Corp.

County Graham

Address: 8223 Willow Place
Suite 250
Houston, Texas 77070-5623

Well total depth 4230 feet **137.47**
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 92 feet
w/100 sx.

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M Day: 30 Month: October Year: 91

Plugging proposal received from: Roy Richmeier

Company: Citation Oil & Gas Corp. Phone:

Were: 5 1/2" casing set at 4023' w/100 sks. cement. Perfs. at 3772' to 3985'. Perf. anhy. at 2150'. Perf. base dakota at 1250'.
Ordered 400 sks. 65/35 poz. - 10% gel. with 1/4 lb. flocele plus 700#
hulls.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All , Part , None

Completed: Hour: 3:00P.M. Day: 30 Month: October Year: 91

Actual plugging report: 10-24-91. R.U. unit to drill out 3 C.I.B.P.'s to cement well. 10-24-91 to 10-29-91 drilling out C.I.B.P.'s for cementing. T.D. 3969'. 10-25-91 R.I.H. w/open ended tubing to 3905'. Spot 90 sx. cement w/400# hulls (31 bbls. slurry). Pulled tubing to 2100'. Perf. casing @ 2150'. Spot 100 sx. cement (35 bbls. slurry). Pulled tubing to 1200'. Perf. casing @ 1250'. Spot 40 sx. cement to circulate at surface. P.O.D.H. with tubing. Hooked up to 5 1/2" casing. Squeezed 35 sx. cement. Max. P.S.I. 1100#. S.I. 1000#.
Hooked up to 8 5/8" S.P. Squeezed 100 sx. cement w/100# hulls.
Remarks: Max. P.S.I. 250#. S.I. 100#.
Cemented through tubing.

I did not observe the plugging.

Dennis L. Hamel

DATE 11-25-91
INV. NO. 33845

J. S.

(agent)
Form CP-2/3