

1-20

4-032204

15-065-03247-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1958

NW SW SE /4 SEC. 10, 10, 25 W
990 feet from S section line
2310 feet from E section line

Operator license# 3553

Lease: Elrick Well # 6-2

Operator: Citation Oil & Gas Corporation

County: Graham

Address: 8223 Willow Place South
Suite #250
Houston, Texas 77070

Well total depth 4001 ^{130.03} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 164 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 20 Month: January Year: 1997

Plugging proposal received from: Citation Staff - Attn: Chris Morro

Company: Citation Oil & Gas Corporation Phone:

Were: Order 225 sxs 60/40 pozmix - 6% gel - 500# hulls.
Halliburton Cement Company.

1-30-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:00 P.M., Day: 20, Month: January, Year: 1997

Actual plugging report: 8 5/8" set at 164' w/100 sxs cwc. 5 1/2" set at 4001' with 100 bbl black magic. D.V. at 2173' w/150 sxs. Prod. Perfs 3774' - 3975'. CIBP 3720'. Critical control shots at 2500' - 2150' - 1250'. Free at 1140'. Mixed and pumped 5 1/2" - 100 sxs cement with 300# hulls. Pulled to 250'. Mixed and pumped 80 sxs cement with 150# hulls to circulated. Pulled casing. Topped off with 20 sxs cement. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

INVOICED I did/did not [X] observe the plugging.

Carl Goodrow (agent)

DATE 2-3-97

INV. NO. 47493