

10-24  
4-041338 15-065-03145-0001R 56

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 6-30-59  
SE SE SE 1/4 SEC. 10, 10 S, 25 W  
330 feet from S section line  
330 feet from E section line

Operator license# 3553 Lease Elrick Unit well # 6-7

Operator: Citation Oil & Gas Corp. County Graham 136.98

Address: 8223 Willow Place Well total depth 4215 feet  
Suite 250 Conductor Pipe: 0 inch @ 0 feet  
Houston, Texas 77070-5623 Surface pipe 8 5/8 Inch @ 114 feet  
w/80 sx.

Aband. oil well    , Gas well    , Input well X, SWD    , D & A    

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00P.M Day: 18 Month: October Year: 91

Plugging proposal received from: Roy Richmeier

Company: Citation Oil & Gas Corp. Phone:                     

Were: 5 1/2" casing set at 4024' w/100 sks. cement. Perfs. at 3748'  
to 3962'. Perf. anhy. at 2150'. Perf. base dakota at 1250'.  
Ordered 400 sks. 65/35 poz. - 10% gel. - with 1/4 lb. flocele plus  
700# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1991

Plugging Proposal Received by: Dennis L. Hamel CONSERVATION DIVISION  
Wichita, Kansas

Plugging operations attended by agent? All  ], Part  ], None  ]

Completed: Hour: 2:15P.M. Day: 24 Month: October Year: 91

Actual plugging report: 10-17-91. R.I.H. with tools, hit bridge @  
1510'. Mudded up. Cleaning out casing (10-19-91 to 10-24-91) to depth  
of 3941'. 10-24-91 R.I.H. with open ended tubing to 3905'. Spotted  
90 sxs. cement (33 bbls. slurry) w/400# hulls in cement. Pulled tubing  
to 2122'. Perf. casing @ 2150'. Spot 100 sx. cement (37 bbls. slurry).  
Pulled tubing to 1200'. Perf. base dakota @ 1250'. Spot 60 sx. cement  
(22 bbls. slurry) to circulate at surface. P.O.D.H. with tubing. Hooked  
up to 5 1/2" casing. Squeezed add. 70 sxs. cement w/200# hulls in  
cement. Max. P.S.I. 850#. S.I. P.S.I. 500#. Hooked up to 8 5/8"  
Remarks: annulus. Squeezed 80 sx. cement w/100# hulls (30 bbls. slurry)  
Max. P.S.I. 450# S.I. P.S.I. 200#  
Cemented through tubing.

I did observe the plugging.  I did not observe the plugging.

*Dennis L. Hamel*

INVOICED

DATE 11-25-91  
INV. NO. 33848

*Gib. S.*

(agent)  
Form CP-2/3