

4-041770

065-03241-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- ~~4-001,723~~

*5-2  
Muker  
Section 3 Salvage  
P.O. Box 205  
Class 1 Xs 67524*

NE SE SW /4 SEC. 10 , 10 S, 25 W  
990 feet from S section line  
2970 feet from E section line

Operator license# 3553

Lease: Elrick Unit Well # 7-4

Operator: Citation Oil & Gas Corp.

County: Graham

Address: 4848 SW 36th Street  
Oklahoma City, OK 73179

Well total depth 3994 <sup>129.80</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 165 feet  
w/115 sxs.

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License#     

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 2 Month: May Year 1996

Plugging proposal received from: Jeff Stevenson

Company: Citation Oil & Gas Corporation Phone:     

Were: 5 1/2" casing set at 3994' w/100 sxs cement. Perf. at 3749' - 3970'.  
Ordered 250 sxs. 60/40 pozmix -10% gel plus 500# hulls.  
Plug bottom C.I.B.P. at 3700' with 2 sxs cement on plug.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 9:30 P.M., Day: 2, Month: May, Year: 1996

Actual plugging report: Spotted 160 sxs cement at 2150' with 300# hulls. Spotted 80 sxs cement at 1250' with 200# hulls. Circulated cement at 200' to surface with 50 sxs cement. Pulled casing with cement in cellar.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 15 1996

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD       
Bottom plug(in place): YES X, CALC     , NO       
Plugged through TUBING     , CASING X.  
Anhy. plug? YES X NO       
Dakota plug: YES X, NO       
Elevation:      GL

I did[      ] / did not[ X ] observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED  
DATE 5-23-96  
INV. NO. 45623