

4-060850

15-065-03288-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-1

API Number: 15- - 1-23-59

NW SW NE /4 SEC. 15, 10 S, 25 W
3630 feet from S section line
2310 feet from E section line

Operator license# 3553

(Formerly Pfeifer #4)
Lease: Elrick Well # 3-4

Operator: Citation Oil & Gas, Inc.

County: Graham

Address: 8223 Willow Place South #250
Houston, Texas 77070-5623

Well total depth 3995 129.83 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 203 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 12:00 P.M. Day: 1 Month: March Year: 1996

Plugging proposal received from: Rich McEntire/Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 150 sxs 60/40 posmix - 10% gel and hulls.
Records on well lost during several transfers of ownership. Twin drilled in 1969 -
100' north of well for injection/SWD apparently replacement for lost hole.

3-13-96

RECEIVED COMM
KANSAS CORP
MAR 13 10 44 AM '96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30 P.M. Day: 1 Month: March Year: 1996

Actual plugging report: 8 5/8" to 203 . 5 1/2" to 3995'. Appears from sketchy records
that well was being squeezed in Cedar Hill Section. During drilling out of cement, operator
got out of hole at 1800'. Confirmed TD with wireline. Ran tubing to 1750' and pumped 60 sxs
cement. Pulled tubing to 900' and circulated cement with 60 sxs. Pulled tubing and tied
onto annulus. Pumped 15 sxs cement with lock up. S.I.P. 400#. Tied onto production casing
and pumped 15 sxs cement. Max. P.S.I. 400#. S.I.P. 400#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2481 GL

I did / did not observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

INVOICED

DATE

MAR 26 1996

INV. NO.

45125