

4-032201

15-065-03287-0000

1-14

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1958

NW NE NE /4 SEC. 15, 10, 25 W  
4950 feet from S section line  
990 feet from E section line

Operator license# 3553

Lease: Elrick Well # 3-2

Operator: Citation Oil & Gas Corporation

County: Graham 130.78

Address: 8223 Willow Place South  
Suite #250  
Houston, Texas 77070

Well total depth 4024 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 237 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 14 Month: January Year: 1997

Plugging proposal received from: Citation Staff - Attn: Chris Morro

Company: Citation Oil & Gas Corporation Phone:

Were: Order 300 sxs 60/40 pozmix - 6% gel - 500# hulls. 1-24-97  
Halliburton Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 5:30 P.M., Day: 14, Month: January, Year: 1997

Actual plugging report: 8 5/8" set at 237' w/175 sxs. cwc. 5 1/2" set at 4024' with 175 sxs.  
Prod. Perfs 3756' - 3995'. C.I.B.P. at 3685'. D.V. Tool at 2160' cement not available.  
Dumped 2 sxs common cement on C.I.B.P. with bailer. Critical control shots at 2500' 2150' and  
1250'. Shot free and recovered 875' of 5 1/2" casing. Mixed and pumped down 5 1/2" 100 sxs  
cement blend. Pulled to 280'. Mixed and pumped 80 sxs cement blend to circulate. Pulled  
5 1/2" casing - topped off with 20 sxs cement blend. Used total of 200 sxs cement blend with  
450# hulls mixed in. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: GL

I (did) (did not) observe the plugging.

Carl Goodrow  
(agent)

INVOICED  
DATE JAN 28 1997  
INV. NO. 42457