

10-10

58

4 - 041337

15-065-03153-0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-26-60

SW NW NW 1/4 SEC. 14, 10 S, 25 W
4290 feet from S section line
4950 feet from E section line

Operator license# 3553

Lease Elrick Unit well # 2-1

Operator: Citation Oil & Gas Corp.

County Graham 137.47

Address: 8223 Willow Place
Suite 250
Houston, Texas 77070-5623

Well total depth 4230 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 129 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M Day: 10 Month: October Year: 91

Plugging proposal received from: Roy Richmeier

Company: Citation Oil & Gas Corp. Phone:

Were: 5 1/2" casing set at 4015' w/100 sks. cement. Perfs. at 3756'
to 3970'. Perf. anhy. at 2150'. Perf. base dakota at 1250'. W.H.M.
to 3985'. P.B.T.D. 3990'. Ordered 400 sks. 65/35 poz. - 10% gel. -
with 1/4 lb. flocele plus 700# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All], Part], None]

Completed: Hour: 2:30P.M, Day: 10, Month: October, Year: 91

Actual plugging report: R.I.H. with tubing to 3900'. Spot 90 sx.
cement w/400# hulls (33 bbls. slurry). Pulled tubing to 2122'. Perf.
anhy. @ 2150'. Spot 100 sx. cement w/200# hulls (37 bbls. slurry).
Pull tubing to 1200'. Perf. B. dakota @ 1240'. Spot 60 sxs. cement
(25 bbls. slurry) to circulate @ surface. P.O.D.H. with tubing,
squeezed 50 sxs. cement (20 bbls. slurry) in 5 1/2" casing. 800# max.
P.S.I. P.S.I. 400#. Hooked up to 8 5/8" S.P. Squeezed 75 sxs. cement
w/50# hulls. Max. P.S.I. 300. S.I. P.S.I. 100#

Remarks: Cemented through tubing.
No C.I.B.P. @ 3700' as reported.

I did I did not observe the plugging.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Dennis L. Hamel

DATE 11-25-91
INV. NO. 33846

J.S.

NOV 14 1991
CONSERVATION DIVISION
Wichita, Kansas

(agent)
For CP-2/3