

10-17
15-065-03154-0000 59
R

4-041340

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 8-25-60
NW NW NW /4 SEC. 14, 10 S, 25 W
4950 feet from S section line
4950 feet from E section line

Operator license# 3553 Lease Elrick Unit well # 2-2

Operator: Citation Oil & Gas Corp. County Graham 137.63

Address: 8223 Willow Place Well total depth 4235 feet
Suite 250 Conductor Pipe: 0 inch @ 0 feet
Houston, Texas 77070-5623 Surface pipe 8 5/8 Inch @ 92 feet
w/100 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M Day: 16 Month: October Year: 91

Plugging proposal received from: Roy Richmeier

Company: Citation Oil & Gas Corp. Phone:

Were: 5 1/2" casing set at 4014' w/100 sks. cement. Perfs. at 3764'
to 3977'. Perf. anhy. at 2150'. Perf. base dakota at 1250'.
Ordered 400 sks. 65/35 poz. - 10% gel. with 1/4 lb. flocele plus 700#
hulls.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1991'

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All], Part], None]
Wichita, Kansas

Completed: Hour: 12:30P.M., Day: 17, Month: October, Year: 91

Actual plugging report: 10-16-91. R.I.H. with tubing and bit to 3600'.
Mudded up. Drilled out C.I.B.P. to 3963'. Circulated 1 hr. P.O.D.H.
with tubing. Shut down. 10-17-91. R.I.H. with tubing to 3905'. Break
circulate. Spotted 90 sx. cement (33 bbls. slurry) w/400# hulls.
Pulled tubing to 2127'. Perf. casing @ 2150'. Spot 100 sx. cement.
(37 bbls. slurry). Pulled tubing to 1200'. Perf. dakota base @ 1250'.
Spot 25 sx. cement (9 bbls. slurry) w/200# hulls. P.O.D.H. with tubing.
Hooked up to casing. Squeezed add. 75 sx. cement (25 bbls. slurry).
Max. 900#. S.I. 500#. Hooked up to 8 5/8" S.P. Squeezed 125 sx. cement
Remarks: w/100# hulls (52 bbls. slurry). Max. 400#. S.I. 100#.
Cemented through tubing.

I **INVOICED** did not observe the plugging.

Dennis L. Hamel

DATE 11-25-91
INV. NO. 33847

Jill S

(agent)
Form CP-2/3