

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-19006-00-01
Spot: SESESW Sec/Twnshp/Rge: 14-10S-25W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: KNOLL B Well Number: 1
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING
Address: 598 - 2ND AVE.
BEAVER, KS 67525

Conductor Pipe: Size feet: 130.65
Surface Casing: Size 8.625 feet: 200
Production: Size 4.5 feet: 4020
Liner: Size feet:

Well Type: EOR UIC Docket No: E12249.1 Date/Time to Plug: 06/18/2002 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICK SCHREIBER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3605

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 325 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/18/2002 12:00 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 200' w/150 sxs cement.
4 1/2" casing at 4020' w/175 sxs cement.
Ran tubing to 1921' - circulated with 240 sxs cement and 500# hulls.
Pulled all tubing and squeezed 4 1/2" casing with 20 sxs cement to Max. P.S.I. 600#. S.I.P. 300#.
Tied to 8 5/8" x 4 1/2" annulus and squeezed 50 sxs to Max. P.S.I. 100#. S.I.P. 100#.
Total of 310 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED
6-27-02
JUN 27 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. CHEYENNE TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-28-02

INV. NO. 2002062019

JUN 25 2002

HERNDON DRLG CO

#1 KNOLL 'B'

14-10-25W
SE SE SW

Contr. HERNDON DRLG GRAHAM County

E 2463RB Comm. 9-24-59 Comp. 12-4-59 IP 98 BOPD

Tops	Depth	Datum
Awk	2101	
HEEB	3738	-1275
KC	3777	-1314
TD	4020	-1557

Casing
8" 200
4" 4020
DST 3748-3821/1 HR, 720° OCM,
30' O, BHP 1180#
DST 3920-64/1 HR, 10° O SPK M
BHP 300#
PERF 16/3808-12: ACID 1000: SWB
5 BWPB: PB 3800: 20/3777-82:
ACID 1000: SWB 10 BOPB, NW/5 HRS
ELRICK SE

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS