

35. -

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-23523-00-00
Spot: NENWSW Sec/Twnshp/Rge: 22-22S-19E
2480 feet from S Section Line, 4181 feet from E Section Line
Lease Name: CLEAVER/CUNNINGHAM Well #: 7
County: ANDERSON Total Vertical Depth: 883 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6	20		6 SX
PROD	2.875	882		62 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2009 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: TIE TO 2 7/8" - ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT. BELOW GROUND LEVEL, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed 11/06/2009 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 830 FEET, STOP WITH POOR CIRCULATION. RUN 1-INCH TUBING TO 675 FEET, STOP WITH POOR CIRCULATION. RUN 1-INCH TUBING TO 520 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT AND COTTON SEED HULLS THEN PRESSURE TO 1100 POUNDS TO SHUT IN. A TOTAL OF 133 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

RECEIVED
JAN 21 2010 LS
KCC Chanute Dist. #3

Perfs:

Top	Bot	Thru	Comments
825	849		

INVOICED
DATE 3/08/10
INV. NO. 2010060885

RECEIVED
JAN 28 2010

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed [Signature]
(TECHNICIAN)