

735-

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-23418-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 22-22S-19E
2197 feet from S Section Line, 4808 feet from E Section Line
Lease Name: CLEAVER/TINSLEY Well #: 5
County: ANDERSON Total Vertical Depth: 883 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6	20		6 SX
PROD	2.875	877		65 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2009 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: TIE TO 2 7/8" - ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT. BELOW GROUND LEVEL, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed 11/06/2009 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 847 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 1050 POUNDS TO SHUT IN. A TOTAL OF 108 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
824	856		

RECEIVED
JAN 28 2010

RECEIVED

JAN 21 2010

LS

KCC Chanute Dist. #3

INVOICED

DATE

3/08/10

INV. NO.

2010060885

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed



(TECHNICIAN)