

#35-

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-01816-00-00
Spot: SENESW Sec/Twnshp/Rge: 22-22S-19E
1971 feet from S Section Line, 2825 feet from E Section Line
Lease Name: CLEAVER-TINSLEY Well #: CLT-03
County: ANDERSON Total Vertical Depth: 735 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

Well Type: OG UIC Docket No: Date/Time to Plug: 09/26/2009 10:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: SOUTHERN STAR Phone: (785) 448-2524

Proposed Plugging Method: PLUG WELL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/26/2009 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 3/4 INCH INSIDE 1.5 INCH CASING TO 735 FEET AND RUN 1 INCH OUTSIDE TO 500 FEET AND PUMP TYPE A PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 161 SACKS OF CEMENT. CONTRACTOR STATED THERE MAY HAVE BEEN A HOLE IN THE CASING BETWEEN 400 AND 500 FEET AS MORE CEMENT WAS USED THAN NORMAL.

INVOICED
DATE 3/08/10
INV. NO. 2010060885

RECEIVED

JAN 21 2010 LS

KCC Chanute Dist. #3

RECEIVED
JAN 28 2010

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed R. D. [Signature]

(TECHNICIAN)