

# 94.12

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20242-00-00  
Spot: NE Sec/Twnshp/Rge: 19-27S-40W  
3907 feet from S Section Line, 1343 feet from E Section Line  
Lease Name: LANE GALEN AND IRIS Well #: 1  
County: STANTON Total Vertical Depth: 2896 feet

Operator License No.: 5707  
Op Name: INTER-AMERICAN ENERGY CORP.  
Address: 260 ADELAIDE ST E PO BOX 191  
TORONTO, CANADA, M5A

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2400		WITH 2 SX CMT
SURF	8.625	778		WITH 450 SX CMT
PROD	4.5	2871	0	WITH 650 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2010 11:00 AM  
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.  
Proposal Rcvd. from: JOE BROUGHER Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2010 2:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

**\*\*CASING LEAK BETWEEN 1000-1100' \*\* CIBP @ 2400' WITH 2 SX CMT. RIH W/TBG TO 1250'. PUMPED 250# HULLS & 150 SX CMT. FILLED 4 1/2" TO SURFACE. CLOSED IN BACKSIDE AND PRESSURED 4 1/2" TO 500 PSI. HELD. PULL OUT OF HOLE WITH TBG & TOPPED OFF 4 1/2" W/CMT. PUMPED 10 SX CMT DOWN 4 1/2" & 8 5/8" ANNULUS. PRESSURE TO 500 PSI.**

Perfs:

RECEIVED  
MAR 04 2010  
KCC WICHITA

INVOICED  
DATE 3/10/10  
INV. NO. 2010060937

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Jack MacClaskey  
(TECHNICIAN)

RECEIVED  
FEB 26 2010  
KCC DODGE CITY

Form CP303