

# 87.23

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00247-00-00  
Spot: SW Sec/Twnshp/Rge: 20-22S-32W  
1381 feet from S Section Line, 3918 feet from E Section Line  
Lease Name: ELY FEE - C Well #: 1  
County: FINNEY Total Vertical Depth: 2684 feet

Operator License No.: 30269  
Op Name: ARGENT ENERGY, INC.  
Address: 1313 N WEBB RD STE 210  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	315		CIRC TO SURF
PROD	2.875	2684		UNK

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2009 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: EARL OCHAMPAUGH Company: ARGENT ENERGY Phone: (620) 272-1219

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/02/2009 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 2650'. 1ST PLUG PUMPED 20 SX CMT & 100# HULLS. WOULD NOT HOLD PRESSURE. 2ND PLUG WAIT 2 HOURS. PUMPED 25 SX CMT & 100# HULLS. SHUT IN PRESSURE 1000#. 3RD PLUG PERFORATED TBG @ 1026'. COULD NOT PUMP INTO. PERFORATED TBG @ 1000'. COULD NOT PUMP INTO. PERFORATED TBG @ 900' RATE 1.5 BPM @ 1050#. MIXED & PUMPED 75 SX CMT, 100# HULLS, & 35 SX CMT. SHUT IN PRESSURE 500#. 4TH PLUG MIXED & PUMPED 180 SX CMT DOWN 2 7/8" X 8 5/8: ANNULUS. SHUT IN PRESSURE 250#.

Perfs:

Top	Bot	Thru	Comments
2596	2615		

INVOICED  
DATE 3/10/10  
INV. NO. 2010060938

RECEIVED  
DEC 24 2009  
KCC WICHITA

Remarks: USED COMMON CMT & 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
DEC 14 2009  
KCC DODGE CITY

Form CP-113