

\$ 80.31

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19576-00-00

Spot: NWNWNW

Sec/Twnshp/Rge: 26-28S-7E

4934 feet from S Section Line, 4941 feet from E Section Line

Lease Name: REMP

Well #: 3

County: BUTLER

Total Vertical Depth: 2471 feet

Operator License No.: 5420

Op Name: WHITE & ELLIS DRILLING, INC.

Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	106		60 SX
PROD	4.5	2464		60 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/24/2009 8:00 AM

Plug Co. License No.: 5870

Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: DALLAS FLOWERS

Company: WHITE & ELLIS DRILLING

Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/24/2009 2:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/CIBP ON WIRELINE AND SET @ 2400', DUMP BAILED 2 SXS CEMENT ON TOP. PRESSURED CASING @ 200#, HELD OK. PERFORATED SQUEEZE HOLES @ 250', SWEDGED INTO 4-1/2" CASING, CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 128 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11-24-2009, 2:00 PM. CONSOLIDATED CEMENT TICKET #23181.

Perfs:

Top	Bot	Thru	Comments
2464	2471	OH	
RECEIVED DEC 29 2009 KCC WICHITA INVOICED DATE <u>3/08/10</u> INV. NO. <u>2010060878</u>			

Remarks: GPS - LAT: 37.59160 LONG: 96.64073

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

JK