

\$ 144.04

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21589-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 11-19S-25W
2983 feet from S Section Line, 2264 feet from E Section Line
Lease Name: PRICE Well #: 1
County: NESS Total Vertical Depth: 4432 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY STE 730 1040
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	450		WITH 250 SX CMT
DVT		1668		WITH 350 SX CMT
PROD	4.5	4260	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2009 1:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS THEN 4 SX CMT. RUN TBG TO 1700' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2009 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report: SAND TO 4040' & 4 SX CMT. RUN TBG TO 1717' & PUMP 105 SX CMT. CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 15 SX CMT. TIE ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:
INVOICED
DATE 3/08/10
INV. NO. 2010060879

RECEIVED
DEC 18 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.
Plugged through: TBG

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED
DEC - 3 2009
KCC DODGE CITY

Form 09-23