

\$ 117.33

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22602-00-00
Spot: SENENE Sec/Twnshp/Rge: 36-14S-14W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: STRECKER JULIUS B Well #: 5
County: RUSSELL Total Vertical Depth: 3610 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	331	0	w/235 sxs cmt
PROD	5.5	3163	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/15/2009 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LUKE DYKES Company: YOUNGER ENERGY COMPANY Phone: (316) 681-2542

Proposed
Plugging
Method:

Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
CIBP in the well at 2820' - had tubing hung in the well - got it out.
Got sandline drill - hung up trying to knock out the plug.
Got the sandline drill out of the well.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2009 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2785' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 2000' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1000' - pumped 125 sxs cement.
Cement circulated out Braden head and backside.
POOH. Pumped 25 sxs cement down casing - circulated out Braden head.
Shut in and topped off casing.

Perfs:

INVOICED
DATE 3/08/10
INV. NO. 2010060881

Remarks: COPELAND CEMENTING-TICKET #35648.

Plugged through: TBG

RECEIVED
DEC 21 2009
KCC WICHITA


District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

DEC 16 2009

ROSEL ENERGY, INC. 36-14-14W
P.O. BOX 1068 #5 'B' JULIUS STRECKER SE NE NE
LIBERAL, KS. 67901
CONTR REVLIN DRILLING CTY RUSSELL
GEOL HERB DEINES FIELD HALL-GURNEY
ELV 1738 KB SPD 7/22/85 CARD ISSUED 10/10/85 IP P 88 BOPD, NW
1733 GL LKC 3130-3132



SMP	Tops	Depth/Datum
ANH		692+1046
TARK		2301- 563
TOP		2576- 838
LKC		2872-1134
RTD		3165-1427
NO LOG		

API 15-167-22,602
8 5/8 " 331 / 235SX, 5 1/2 " 3163
NO DSTS ~~258-260~~
MCT - CO, PF (LKC) 3130-32, W / 4 SPF, SWB DWN, NAT, T&R,
POP, P 88 BOPD, NW, 8/15/85