

#104.59

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22434-00-00  
Spot: NESESW Sec/Twnshp/Rge: 31-27S-7E  
833 feet from S Section Line, 2770 feet from E Section Line  
Lease Name: FARNER Well #: 7  
County: BUTLER Total Vertical Depth: 3218 feet

Operator License No.: 5387 *AZTEC OIL CO. DIVISION*  
Op Name: THE BUCKEYE CORPORATION DBAA  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204		90 SXS CMT
PROD	4.5	2782	920	75 SXS CMT

*See well log*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2009 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: STEVEN W KILE Company: AZTEC OIL CO Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2009 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:  
RIH W/TBG @ 2,544', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A COMMON 3% CC, AND DISPLACED IN CASING. WAITED ON CEMENT 2 HOURS, TAGGED CEMENT @ 2250'. CUT CASING @ 1250', & 920', LAYED DOWN 23 JTS (920') 4-1/2" CASING. RIH W/TBG @ 310', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:00 PM 11-18-2009. CONSOLIDATED CEMENT TICKET #23133. 11-19-2009. TOPPED WELL OFF TO SURFACE W/30 SXS.

Perfs:

Top	Bot	Thru	Comments
2716	2726		CSG

**INVOICED**  
DATE 3/08/10  
INV. NO. 2010060882

**RECEIVED**  
**DEC 29 2009**  
**KCC WICHITA**

Remarks:  
Plugged through: TBG

District: 02 Signed Duane Krueger  
(TECHNICIAN)

*1/8*