

#103.97

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23033-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 6-28S-7E  
4403 feet from S Section Line, 1978 feet from E Section Line  
Lease Name: HOUSTON Well #: 7  
County: BUTLER Total Vertical Depth: 3199 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205		85 SX CMT
PROD	5.5	3193	723	100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2009 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: STEVEN W KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PERKCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/25/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING HOLE CLEAN TAGGED SOLID @ 2,775'. POSSIBLY OUTSIDE CASING. PULLED TBG BACK @ 2,744' CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION., MIXED & PUMPED 75 SXS CLASS A COMMON 35 CC, AND DISPLACED IN CASING. WAITED ON CEMENT 2 HOURS. TAGGED CEMENT @ 2250'. CUT CASING @ 723', LAYED DOWN 18 JTS (723') 5-1/2" CASING. RIH W/TBG @ 310', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCUALTION, MIXED & PUMPED 126 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M. 11-25-2009. CONSOLIDATED CEMENT TICKET #23136.

Perfs:

Top	Bot	Thru	Comments
3182	3184	CSG	
2749	2752	CSG	

INVOICED  
DATE 3/08/10  
INV. NO. 2010060882

RECEIVED  
DEC 29 2009  
KCC WICHITA

Remarks: LAT: 37.64765, LONG: 96.70398

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

14