

#35-

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-21880-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 14-21S-19E
226 feet from S Section Line, 5080 feet from E Section Line
Lease Name: BENJAMIN Well #: 3
County: ANDERSON Total Vertical Depth: 830 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.625	55		
PROD	4.5	872		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2009 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: WORK STRING RUN TO BOTTOM, CEMENT TO SURFACE, SQUEEZE UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: RUSSELL HINE WitnessType: NONE
Date/Time Plugging Completed 11/05/2009 3:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 830 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 250 POUNDS TO SHUT IN. A TOTAL OF 93 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
830	838		
821	826		
814	816		
803	808		

RECEIVED
KCC DISTRICT #3

DEC 10 2009

CHANUTE, KS

LS


INVOICED
DATE 3/08/10
INV. NO. 2010060884

Remarks:

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)
RECEIVED

DEC 14 2009

Form CP-2/3

KCC WICHITA