

\$35-

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-003-21914-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 14-21S-19E  
651 feet from S Section Line, 5078 feet from E Section Line  
Lease Name: BENJAMIN Well #: 4  
County: ANDERSON Total Vertical Depth: 830 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.625	50		
PROD	4.5	863		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2009 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BERNIE ROCKERS Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: WORK STRING RUN TO BOTTOM, CEMENT TO SURFACE, SQUEEZE UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE  
Date/Time Plugging Completed 11/05/2009 2:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 830 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 200 POUNDS TO SHUT IN. A TOTAL OF 82 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
821	829		
805	815		

RECEIVED  
KCC DISTRICT #3  
DEC 10 2009  
CHANUTE, KS

INVOICED  
DATE 3/08/10  
INV. NO. 2010060884

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 14 2009

KCC WICHITA