

#35

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-22008-00-00
Spot: NESWSW Sec/Twnshp/Rge: 14-21S-19E
690 feet from S Section Line, 4193 feet from E Section Line
Lease Name: BENJAMIN Well #: 13
County: ANDERSON Total Vertical Depth: 847 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 6.625 | 80 | | 25 SX |
| PROD | 4.5 | 853 | | 115 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2009 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: WORK STRING RUN TO BOTTOM, CEMENT TO SURFACE, SQUEEZE UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: RUSSELL HINE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 11/04/2009 5:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 847 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 600 POUNDS TO SHUT IN. A TOTAL OF 79 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 800 | 816 | | |

RECEIVED
KCC DISTRICT #3
DEC 10 2009 LS
CHANUTE, KS

INVOICED
DATE 3/08/10
INV. NO. 2010060884

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

RECEIVED
DEC 14 2009
KCC WICHITA