

\$162.50

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22211-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 11-19S-28W
931 feet from N Section Line, 2083 feet from E Section Line
Lease Name: SCHWARTZ Well #: 11-1
County: LANE Total Vertical Depth: 5000 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	331		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/05/2010 2:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY TALBOT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 02/05/2010 4:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
DATE 3/10/10
INV. NO. 2010060930

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael Maier/afj
(TECHNICIAN)