

#35.-

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-003-22256-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 14-21S-19E  
482 feet from S Section Line, 4812 feet from E Section Line  
Lease Name: BENJAMIN Well #: INJ 4  
County: ANDERSON Total Vertical Depth: 805 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	879		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2009 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BERNIE ROCKERS Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: SQUEEZE UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT. BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: RUSSELL HINE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 11/04/2009 3:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 805 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 1,100 POUNDS TO SHUT IN. A TOTAL OF 38 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
816	840		
806	812		

RECEIVED  
KCC DISTRICT #3  
DEC 10 2009 LS  
CHANUTE, KS


INVOICED  
DATE 3/08/10  
INV. NO. 2010060884

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

DEC 14 2009

KCC WICHITA