

15
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name Hobbs Well No. 1

Location N/2-N/2-NW Sec. 18 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3963

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. _____

Operation Completed: Hour 2:45 PM Day 13 Month 1 Year 1969

The Above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1280'.

Circulated hole with heavy mud, pulled DP to 1450' and displaced 100 Sx. cement from
1450' to 1125'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215' to
155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/16/69
INV. NO. 9196-u

RECEIVED
STATE CORPORATION COMMISSION
1-16-1969
JAN 16 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: *W. L. DeShob*
Well Plugging Supervisor