

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
MAY 20 1967
11-20-1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Empire Drilling Company,
Complete Address 650 4th National Bank Building, Wichita, Kansas.
Lease Name Hobbs Well No. 1
Location SE-SW-NE Sec. 18 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 4000'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated,
Address Box # 486, Great Bend, Kansas. License No.
Operation Completed: Hour 12:45AM Day 18 Month 11 Year 1967

The above well was plugged as follows:

186'--8 5/8" Surface pipe, cement circulated with 135 Sx.
Dakota section from 950' to 1150'.

Circulated hole with heavy mud. Pulled DP to 1170' and displaced 100 Sx. cement thru
DP from 1170' to 850'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'
to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/21/67
INV. NO. 6911-w