

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

DEC 26 1967
12-26-1967

Operator's Full Name Empire Drilling Company,

Complete Address 650 4th National Bank Building, Wichita, Kansas.

Lease Name Hobbs Well No. 2

Location 2640' WEL & 440' SNL-NE 1/4 N 1/2 N 1/2 Sec. 18 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 8:30 AM Day 22 Month 12 Year 1967

The above well was plugged as follows:

221'--8 5/8" Surface pipe, cement circulated.
Dakota section from 950' to 1160'.

Circulated hole with heavy mud. Pulled DP to 1180' and displaced 100 Sx. cement thru
DP from 1180' to 860'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. D. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/27/67
INV. NO. 6973-4