

15-065-20138-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
5-10-1968  
MAY 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name Dave Rush Well No. A-3

Location NE-NE-SW Sec. 20 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3960

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.     

Operation Completed: Hour 1:00 AM Day 7 Month 5 Year 1968

The Above well was plugged as follows:

174'--8 5/8" Surface pipe, cement circulated with 135 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru  
DP from 1175' to 850'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from  
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 5/10/68  
INV. NO. 7729-W