 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-12-1968
MAR 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name Gay Rush Estate Well No. D-1

Location SE-SE-SE Sec. 20 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leo J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 10:00AM Day 5 Month 3 Year 1968


The Above well was plugged as follows:

171'--8 5/8" Surface pipe, cement circulated with 125 Sx.
Dakota section from 900' to 1100'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru DP
from 1125 to 800'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from 180' to
120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 3/12/68
INV. NO. 4401-W