

15-047-20014-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT -2 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed September 14, 1967.

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.
Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202
Lease Name Robbins "B" Well No. # 1
Location C NW NE Sec. 33 Twp. 26 Rge. 20 (E) W
County Edwards Total Depth 4906'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Walters Drilling Company
Address: 400 Insurance Bldg., Wichita Kansas 67202 License No.
Operation Completed: Hour 9:30AM Day 27th Month Sept. Year 1967

The Above well was plugged as follows:

567' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level
in the hole was at 200'. 1st cementing plug and 1/4 sack of hulls was pushed
in fluid to 400', and cemented with 25 sacks, through the drill pipe, with
cement from 400' to 325'. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed:

Aubrie Elving
Well Plugging Supervisor

INVOICED

DATE 10/2/67INV. NO. 6422-4