

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

2-19-1963  
FEB 19 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Conservation  
Wichita, Kansas

Operator's Full Name D. G. Hansen  
Complete Address: Box #187, Logan, Kansas  
Lease Name Pfeifer Well No. 1  
Location SW-SW-SW Sec. 4 Twp. 10 Rge. (E) (W) 25  
County Graham Total Depth 4110  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Southwest Casing Pulling Co.,  
Address: Box #364, Great Bend, Kansas License No. 399  
Operation Completed: Hour 1:00P Day 13 Month 2 Year 1963

The Above well was plugged as follows:

204' 8 5/8" casing cemented with 200 Sx. cement. 5 1/2" cemented with 125  
Sx cement @ 4108', well plugged back to 4020'. Sanded well back to  
4000', set 4 Sx cement w/dump bailer.. Pulled 1830' 5 1/2" to 550', circulated  
hole with heavy gel mud (17 Sx Gel), displaced 20 Sx cement thru 5 1/2".  
Heavy mud to 180', displaced 20 Sx cement thru 5 1/2" @ 180'. Heavy mud to  
35', set bridge and 10 Sx cement to bottom of cellar.

(Cementing by Sun Oil Well Cementing Inc.)

I hereby certify that the above well was plugged as herein stated.

DATE 2/18/63  
INV. NO. 6603-W

Signed: W. L. Nichol  
Well Plugging Supervisor