

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Pfeifer Well No. B-1

Location NW-NW-SE Sec. 4 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4090'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 4:30 PM Day 28 Month 1 Year 1969

The Above well was plugged as follows:

161'--8 5/8" Surface casing, cement circulated with 125 Sx.  
4087'--4 1/2" Casing cemented on bottom with 125 Sx. Well plugged back to 4054'. Top perforations @ 3812'.

Pushed plug to 3750' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well with 5 sacks hulls and 10 saskc gel initially and followed with 130 Sx. cement from 1225' to 900' then 18 sacks gel from 900 to 180' and followed with 20 Sx. cement from 180' to 120' then 2 sacks gel from 120 to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-100#. (Cementing and mudding operations performed by Sun Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/30/69  
INV. NO. 9255-W

Signed: M. S. Nichel  
Well Plugging Supervisor