

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kimbark E xploration Co.

Complete Address: 201 University Blvd., Denver, Colo.

Lease Name Pfeifer Well No. 1

Location SE-SW-SW Sec. 4 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4070

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 22 Month 2 Year 1964

The Above well was plugged as follows:

196'--8 5/8" Surface pipe, cement circulated. 4070'--4 1/2" production casing
cemented with 100 Sx. Well plugged back to 4030, Top perforations @ 3970'.
Sanded well back to 3960 and set 3 sx. cement with dump bailer.
Pulled 4 1/2" to 600' and circulated heavy gel mud. Pulled 4 1/2" to 540' and
displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 190' and displaced 20 Sx.
cmment thru 4 1/2". Pulled 4 1/2" set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

DATE 2/28/64

INV. NO. 8720-W

FEB 28 1964
2-28-1964

CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. Nichols
Well Plugging Supervisor